

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 28 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Dale Buller of Gabbert-Jones, Inc. has this date requested permission to plug the following described well:

Mr. Buller guarantees payment of the plugging fee.

Operator's full Name: O. A. Sutton

Complete Address: 407 Insurance Bldg., Wichita, Kansas

Lease Name: Day Well No. # 1

Location: C NE NE Sec. 23 Twp. 29 Rge. 6 (E)(W) W

County Kingman Total Depth 4525' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Buller was instructed to plug the well as follows:

272' of 8 5/8" surface pipe, cement circulated with 225 sacks. Fill hole with drilling mud to 250', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Arlene Elving
Conservation Division Agent