

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84
RECEIVED
STATE CORPORATION COMMISSION

2-6-89
FEB 6 1989

WELL PLUGGING APPLICATION FORM
(File One Copy)

CONSERVATION DIVISION
Wichita, Kansas

API NUMBER 15-191-20,527-0000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Anadarko Petroleum Corporation OPERATORS LICENSE NO. 4549

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351 PHONE # (316) 624-6253

LEASE (FARM) Cornelson "A" WELL NO. 1 WELL LOCATION C SW NW COUNTY Sumner

SEC. 7 TWP. 33S RGE. 1 (R) or (W) TOTAL DEPTH 4375 PLUG BACK TD - -

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO.

SURFACE CASING SIZE 8-5/8" SET AT 391 CEMENTED WITH 300 SACKS

CASING SIZE 4-1/2" SET AT 4355 CEMENTED WITH 150 SACKS

PERFORATED AT 4237-42

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Spot 20 sxs cement 4355-4155, load hole with mud, shoot off casing at FP, pump mud and hulls to 500', spot 50 sxs cement 500-300, pump mud and hulls to 40', spot 10 sxs cement 40-0', cut off casing and cap well 3' below ground level.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? No
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN As soon as possible

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Jerry Ruttman PHONE # (316) 624-6253

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351

PLUGGING CONTRACTOR Sargent's Casing Pulling Service LICENSE NO. 6547 6/89

ADDRESS P. O. Box 506, Liberal, Kansas 67905-0505 PHONE # (316) 624-7455

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: M. L. Pease
M. L. Pease, Div. Prod. Mgr. (Operator or Agent)

DATE: 2/2/89

(2)



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
MARGALEE WRIGHT COMMISSIONER
JUDITH McCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

CONSERVATION DIVISION
SHARI M. FEIST, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

THIS NOTICE
MAY 7 1989
EXPIRES

February 7, 1989

WELL PLUGGING NOTICE

Cornelson "A" #1
C SW NW
Sec. 07-33S-01W
Sumner County

Anadarko Petroleum Corporation
P: O. Box 351
Liberal, KS 67905-0351

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist

Shari Feist
Director
State Corporation Commission

DISTRICT #2 202 W. First, Ste. 300, Wichita, KS 67202 (316) 263-8809