

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-025-20,462-0000

LEASE NAME Waits

WELL NUMBER 3-7

1980 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 7 TWP. 32S RGE. 21 (S) or (W)

COUNTY Clark

Date Well Completed 5-27-81

Plugging Commenced 10-23-85

Plugging Completed 10-24-85

LEASE OPERATOR Mesa Petroleum Co.

ADDRESS P.O. Box 2009, Amarillo, Texas 79189

PHONE# (806) 378-1000 OPERATORS LICENSE NO. 5575

Character of Well P&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes 8/4/81 If not, is well log attached? \_\_\_\_\_

Producing Formation Lansing Depth to Top 4534' Bottom 4537' T.D. 6500'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Lansing 4534-37</u>	<u>oil</u>	<u>surface</u>	<u>676</u>	<u>8 5/8"</u>	<u>676'</u>	<u>673'</u>
<u>Viola 6352-6422</u>	<u>oil</u>	<u>surface</u>	<u>6500</u>	<u>5 1/2"</u>	<u>6500'</u>	<u>2345'</u>
<u>CIBP set 4650'</u>	<u>11/8/82; well T&amp;A</u>	<u>11/12/82</u>				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Pumped 30 sx cement plug from 4537-4445'; displaced with 106 bbls 9.0 ppg; WOC 2 hrs - shot casing off at approx 2351', POH 15' with 5 1/2"; POH w/5 1/2" to 1050', pmpd 50 sx 1050-875'; displace with 9.0 ppg mud, pulled casing to 700', spotted 50 sx cmt plug from 700'-530'; pmpd 37' cement plug in 8 5/8", cut surface 3' below GL, welded on dry hole marker.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pullers License No. 6547

Address Liberal, Kansas

STATE OF Texas COUNTY OF Potter, ss.

Carolyn L. Cummings (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Carolyn L. Cummings  
(Address) P.O. Box 2009, Amarillo, TX 79189

SUBSCRIBED AND SWORN TO before me this 29th day of October, 1985

Sturina Potts  
Notary Public  
RECEIVED  
STATE CORPORATION COMMISSION  
My Commission Expires: 8-6-89

XC: WF, CR, Reg, Midland, Acctg, Partners

OCT 31 1985

Form CP-4  
Revised 08-84

