

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-025-20,570 ⁴⁵⁸-0000

LEASE NAME WAITS

WELL NUMBER # 2-7

3300 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 7 TWP. 32S RGE. 21 (E) or (W)

COUNTY Clark

Date Well Completed P&A 10-28-85

Plugging Commenced 10-24-85

Plugging Completed 10-28-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Mesa Petroleum Co.

ADDRESS P.O. Box 2009, Amarillo, Texas 79189

PHONE (806) 378-1000 OPERATORS LICENSE NO. 5575

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Viola Depth to Top 6050 Bottom 6524 T.D. 6530'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Viola</u>	<u>water</u>	<u>6050</u>	<u>6524</u>	<u>8 5/8</u>	<u>675'</u>	<u>0</u>
				<u>4 1/2</u>	<u>6524</u>	<u>3395'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped 30 sx cement plug 6396'-6059', displaced with 92 bbls 9.0 ppg mud; pumped 50 sx cement plug 1000-800', displaced with 12 bbls 9.0 ppg mud; pumped 50 sx cement plug 700-530', displaced with 8 bbls 9.0 ppg mud, set 10 sx cement plug 40'-surface, cut 8 5/8" 3' below GL, welded on dry hole marker

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pullers License No. 6547

Address Liberal Kansas

STATE OF Texas COUNTY OF Potter, ss.

Carolyn L. Cummings (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Carolyn Cummings

(Address) Box 2009, Amarillo, Texas 79189

SUBSCRIBED AND SWORN TO before me this 26th day of December, 1985

My Commission Expires: 8-6-89

Notary Public
STATE CORPORATION COMMISSION

12-30-1985
DEC 30 1985

XC: WF, CR, Reg., Acctg, Expl., Land, Partners