

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER _____
LEASE NAME Baty
WELL NUMBER #1
SPOT LOCATION C-SE SE
SEC. 17 TWP. 32 RGE. 30 (X) or (W)
COUNTY Meade
Date Well Completed 5-27-57
Plugging Commenced 11-27-84
Plugging Completed 11-30-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Warren Angell (Landowner)
ADDRESS Plains Ks.

PHONE # () _____ OPERATORS LICENSE NO. none Required

Character of Well gas
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Ks. #1

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation Chester Depth to top 5630' bottom 36' T.D. 5750'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
Formation	Content	From	To	Size	Put In	Pulled out
Surface				8 5/8"	1612'	0'
Production				5 1/2"	5750'	2800'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.
Pumped 2 sks. hulls & 20 sks. cement to 5350' pressured to 500 lbs.
Pumped 40 sks. cement 1660 to 1560' & displaced w/mud to 800'
Pumped 30 sks. cement 800' to 700' & displaced w/mud to 40'
Put bridge & 10 sks. cement 40' to 0'
Cut-off 8 5/8", 3 1/2 ft. below ground level
(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497
Address Box F, Sublette, Ks. 67877

RECEIVED
STATE CORPORATION COMMISSION

STATE OF KANSAS COUNTY OF HASKELL, ss.

DEC 14 1984
12-14-1984
CONSERVATION DIVISION
Wichita, Kansas

I, Edgar J. Eves (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) Edgar J. Eves
(Address) Box F, Sublette, Ks. 67877

SUBSCRIBED AND SWORN TO before me this 12 day of Dec., 1984

Sandra L. Eves
Notary Public

My Commission expires: 12-6-88

