

STATE OF KANSAS
STATE CORPORATION COMMISSION
207 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 119-20,708-0000

LEASE NAME Lester Davis

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-31

2310 Ft. from S Section Line

2310 Ft. from E Section Line

LEASE OPERATOR Kaiser-Francis Oil Company

SEC. 31 TWP. 32S RGE. 28 (S) or (W)

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

COUNTY Meade

PHONE#(918) 491-4314 OPERATORS LICENSE NO. 6568

Date Well Completed 6/18/85

Character of Well Gas

Plugging Commenced 4/21/93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4/26/93

The plugging proposal was approved on n/a (date)

by n/a (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached?

Producing Formation Morrow Depth to Top 5557 Bottom 5562 T.D. 5800

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Morrow</u>	<u>Gas</u>	<u>5557</u>	<u>62</u>	<u>8 5/8</u>	<u>1400</u>	<u>-0-</u>
				<u>4 1/2</u>	<u>5797</u>	<u>3120</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
MIRU. Set bottom plug from 5560'-5400' w/20 sxs cmt. Displaced w/mud. Shot 4 1/2" casing @ 3120'. POOH & LD. Set 50 sx cmt plug from 1450'-1350'. Set 40 sx cmt plug from 700'-600'. Set 10 sx cmt surface plug from 40'-surface. Job complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service

License No. RECEIVED
STATE CORPORATION COMMISSION

Address P. O. Box 506, Liberal, KS 67901

APR 18 1994

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Sargent's Casing Pulling Service

STATE OF Oklahoma COUNTY OF Tulsa, ss.

CONSERVATION DIVISION
Wichita, Kansas

Charlotte Van Valkenburg (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Van Valkenburg

(Address) P. O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 15th day of April, 19 94

Linda Imhoff
Notary Public

My Commission Expires: 12-24-97