


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Sumner County, Sec. 7 Twp. 33S Rge. 1 (W)

Location as "NE/CNW/SW" or footage from lines NE NE SE
Lease Owner Parker Petroleum, Inc.
Lease Name Sukovaty Well No. 1
Office Address Box 791 - Ponca City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 7-19 1956
Application for plugging filed 7-19 1956
Application for plugging approved 7-19 1956
Plugging commenced 7-19 1956
Plugging completed 7-19 1956
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. G. Buffington
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4415 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Kansas City	No Show	3229		8 5/8	509	
Mississippi	"	3893				
Simpson	"	4284				
Arbuckle	"	4368				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole filled with mud to 509' set with 15 sacks cement. Mud to 35'. Plug set with 10 sacks cement. Hole plugged.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. C. Smitherman Drilling Company
Address Box 627 - Augusta, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.
Joe W. Cain (employee of owner) or (owner/operat) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joe W. Cain
Box 627 - Augusta, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of July, 19 56

My commission expires October 23, 1958.

Ruth H. Carter
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

JUL 27 1956
7-27-1956

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 7 T 33 R 1W
BOOK PAGE 82 LINE 36

SUKOVATY #1

Company - Parker Petroleum, Inc.
 Contractor - L. C. Smitherman Drlg. Co.
 Commenced - 6-30-56
 Completed - 7-19-56
 Total Depth - 4415'
 Initial Prod. - D & A

Location: NE NE SE, Sec. 7-33S-1W,
 Sumner County, Kansas
 Elevation:
 Casing: 8 5/8" - 509' cemented W/300 Sks.

Figures Indicate Bottoms of Formations:

Depth	Formation
0 - 40	Sod - Sand & Shale
40 - 45	River Gravel
45 - 110	Shale & Shells
110 - 350	Shale - Lime - Shells
350 - 425	Lime & Shale
425 - 465	Shell - Lime - Hard
465 - 470	Salt
470 - 490	Lime & Shells
490 - 507	Shale & Shells
507 - 509	Lime
509 - 940	Lime & Shale
940 - 1015	Lime (Ft. Riley)
1015 - 1260	Lime & Shale
1260 - 2000	Shale & Lime
2000 - 2060	Lime & Shale
2060 - 2130	Shale & Lime
2130 - 2190	Lime & Shale Strks.
2190 - 2315	Lime & Shale
2315 - 2487	Lime W/Shale Strks.
2487 - 2785	Lime & Shale
2785 - 2978	Lime W/Shale Strks.
2978 - 3090	Shale & Lime
3090 - 3254	Lime
3254 - 3316	Lime & Shale
3316 - 3365	Lime
3365 - 3457	Lime & Shale
3457 - 3499	Lime & Shale Sandy
3499 - 3586	Lime & Sandy Shale
3586 - 3654	Lime (K.C.)
3654 - 3665	Shale & Lime
3665 - 3753	Lime (Oswego)
3753 - 3789	Shale & Lime
3789 - 3845	Lime & Shale
3845 - 3866	Lime W/Chert Strks.
3866 - 3933	Lime & Chert
3933 - 4037	Lime (Miss.)
4037 - 4060	Lime & Chert
4060 - 4108	Lime (Miss.)
4108 - 4158	Lime & Chert
4158 - 4200	Lime & Shale
4200 - 4211	Lime
4211 - 4327	Sand (Simpson)
4327 - 4355	Dolomite & Lime
4355 - 4415	Dolomite
4415 - R. T. D.	

We hereby certify the above and foregoing to be a true and correct copy of the Log on the Sukovaty #1, located in the NE NE SE, Section 7-33S-1W, Sumner County, Kansas.

L. C. SMITHERMAN DRILLING COMPANY

J. W. Cain (Signature)
 STATE OF KANSAS
 COUNTY OF SUMNER

Subscribed and sworn to before me this 25th day of July, 1956.

PLUGGING
 FILE SEC 7 T 33 R 1W
 BOOK PAGE 82 LINE 36

Kath W. Carter (Signature)
 CONSERVATION DIVISION
 STATE OF KANSAS
 Notary Public

My commission expires October 23, 1958.