

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-129-00105-0000

API NUMBER Completed July 1954

LEASE NAME Saunders

WELL NUMBER 1-22

2310 Ft. from Section Line

2310 Ft. from Section Line

SEC. 22 TWP. 34S RGE. 43 (N) or (W)

COUNTY Morton

Date Well Completed July 1954

Plugging Commenced 2/27/97

Plugging Completed 2/28/97

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Coastal Oil & Gas Corporation

ADDRESS 9 Greenway #2751 Houston TX 77046

PHONE#(713) 877-7590 OPERATORS LICENSE NO. 6593

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on Unknown (date)

by _____ (KCC District Agent's Name).

Is ACO-1 filed? Unknown If not, Is well log attached? Completed Well in 1954 No logs in file

Producing Formation Deer Creek Depth to Top 3106' Bottom 3405'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Wabaunsee	Gas	2725'		8 5/8"	609'	0
Shawnee	Gas	2954'		5 1/2"	3370'	0
Deer Creek	Gas	3106'				
Le Compton	Gas	3242'				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. MIRU well service POOH 63-3/4" Rods, 61-5/8" rod & 2" x 1-1/4 x 12 BBL Pump. POH 10' Jts. 2-3/8" tbg. Remove MA & TIH 103 jts. 2-3/8" tbg to 3200'. Well on vac. Went down to tag plug. Plug @ 2900' mixed & pumped 50 sx 65/35 poz to 2300'. POH & tallied in to 2000'. WOC 4 hrs. & pumped 9# gel (Circ. to surface). POOH to 670' & pump 55 sx. (OVER)
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. _____

Address P.O. Box 1598 Liberal KS 67905

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Coastal Oil & Gas

STATE OF Texas COUNTY OF Harris, ss.

Deborah Moore (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Deborah Moore

(Address) 9 Greenway #2751 Houston TX 77046

SUBSCRIBED AND SWORN TO before me this 4th day of April, 19 97



Tina Jordan Notary Public

Expires: July 5, 1997

Saunders 1-22 Morton County KS

65/35 poz for top plug. POOH. Cut off 8-5/8" & 5-1/2" csg. 3' BGL welded on plate
Hauled rods, tbg. & well enclosure to yard & dress up location.

Gary Winters from KCC on location.

1037 10/17
10/17 10/17
10/17 10/17
10/17 10/17