

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Kingman County, Sec. 27 Twp. 29S Rge. (E) 10 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. ~~C-NE-NW-NE~~

Lease Owner The Carter Oil Company

Lease Name Leo Spade Well No. 1

Office Address Box 786 - Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed December 17 1955

Application for plugging filed June 9 1955

Application for plugging approved June 10 1955

Plugging commenced June 20 1955

Plugging completed June 24 1955

Reason for abandonment of well or producing formation
Uneconomical to Operate

If a producing well is abandoned, date of last production June 17 1955

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

NORTH

Locate well correctly on above
Section Flat

Name of Conservation Agent who supervised plugging of this well Merle Rives

Producing formation Miss. Lime Depth to top 4306 Bottom Total Depth of Well 4880 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Mississippi Lime	Oil	4312	4321	8-5/8"	321	none
				5 1/2"	4712	3546

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged with cement & mud as follows::

Filled with mud from 4800' to 4694'
 cement " 4694' " 4652'
 Ran Lane Wells bridging plug @ 4340'
 cement from 4340' to 4265'
 mud " 4265' " 270'
 cement " 270' " 200'
 mud " 200' " 35'
 Capped with cement " 35' " Top

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 7 1955 7-7-56
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The Carter Oil Company
Address Box 786
Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.

Hugh H. Goerner (District Superintendent) (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) *Hugh H. Goerner*

(Address)

SUBSCRIBED AND SWORN to before me this 6th day of July, 1955

My commission expires Aug 19, 1957

W. H. Kusley
Notary Public.



DRILLER'S LOG
LEO SPADE NO. 1
KINGMAN COUNTY, KANSAS

Sec. 27 - 29S - 10W
C-NE-NW-NE

	From	To
Surface	0	4
Sandy Clay	4	20
Sand	20	95
Redbeds	95	215
Redbeds & Lime shells	215	319
Redbeds & Shale	319	1065
Sandy Shale	1065	1608
Lime & Shale	1608	2357
Sandy Shale & Lime	2357	2557
Lime & Shale	2557	3440
Chalky Lime	3440	3510
Lime	3510	3590
Lime & Shale	3590	3817
Lime	3817	3975
Cherty Lime & Shale	3975	4080
Lime	4080	4139
Lime & Shale	4139	4217
Lime	4217	4243
Lime & Shale	4243	4303
Lime & Chert	4303	4320
Lime	4320	4330
Sandy Lime w/Chert	4330	4350
Lime, Chert & Shale	4350	4372
Lime & Shale	4372	4516
Shale	4516	4596
Lime	4596	4606
Shale & Dolomite	4606	4636
Lime & Dolomite	4636	4692
Hard Sand & Shale	4692	4764
Sand & Shale	4764	4770
Dolomite	4770	4800
Total Depth	4800	

Drilled by:: Shamrock Drilling Company
407 Rule Building
Wichita, Kansas

7-7-55
JUL 7 1955
CONSERVATION DIVISION
Wichita, Kansas

