


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD



Kingman County, Sec. 27 Twp. 29S Rge. (E) 10 (W)  
Location as "NE/CNWKSW¼" or footage from lines C NW NW  
Lease Owner Anadarko Production Company  
Lease Name Spade "A" Well No. 1  
Office Address Box 351, Liberal, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 5-18 19 74  
Application for plugging filed 5-18 19 74  
Application for plugging approved 5-18 19 74  
Plugging commenced 5-18 19 74  
Plugging completed 5-18 19 74  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Biberstein, Attica, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4650 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	306'	None
				4-1/2"	1873'	940'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mixed 30 sacks cement, pumped plug to 1650'. Cut off 4-1/2" casing at 940'. Spotted 35 sacks cement at 250' to 150'; 10 sacks cement 40' to 0'.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 30 1974  
CONSERVATION DIVISION  
Wichita, Kansas  
5-30-74

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Pratt Well Service  
Address Pratt, Kansas

STATE OF KANSAS, COUNTY OF SEWARD, ss.  
T. W. Williams (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me, God.

(Signature) T. W. Williams  
T. W. Williams  
Box 351, Liberal, Kansas 67901  
(Address)

NORMA JEAN TUCKER  
NOTARY PUBLIC  
Seward County, Kansas  
My commission expires September 9, 1976

Subscribed and sworn to before me this 21st day of May, 1974  
Norma Jean Tucker  
Notary Public.

My commission expires \_\_\_\_\_

DRILLER'S LOG

WELL NAME Spade "A" #1 COMPANY OPERATING Anadarko Production Company

ADDRESS OF COMPANY Box 351, Liberal, Kansas

WELL LOCATION NW  $\frac{1}{4}$  NW  $\frac{1}{4}$   $\frac{1}{4}$   
660 Ft. ~~NORTH OF SOUTH LINE~~, South of North Line  
660 Ft. East of West Line, Sec. 27, Twp. 29S, Rge. 10W, Kingman County, Kansas

DRILLING STARTED 4-26, 19 74, DRILLING COMPLETED 5-18, 19 74  
 WELL COMPLETED 5-18, 19 74, WELL CONNECTED \_\_\_\_\_, 19 \_\_\_\_\_

ELEVATION 1738 Ft. Ground Level CHARACTER of WELL (Oil, Gas, Dry Hole) Dry Hole

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used
Winfield	1767	1774	14	Acidized w/1000 gallons 15% Fraced w/ 5000 gallons 3% gelled acid + 5000# 20-40 sand.	

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
8-5/8"	306'	350	None
4-1/2"	1873'	100	940'

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Sand	0	90			
Red bed & shale	90	1320			
Shale	1320	1550			
Lime & shale	1550	4295			
Miss. lime	4295	4550			
Lime & shale	4550	4630			
Sand	4630	4650			
Total Depth	4650				

RECEIVED  
STATE CORPORATION COMMISSION

MAY 30 1974

CONSERVATION DIVISION  
Wichita, Kansas

RESULTS OF INITIAL PRODUCTION TEST: \_\_\_\_\_

5-30-74