


15-18700008-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

STANTON County. Sec. 30 Twp. 29S Rge. 42 (E) W (W)  
Location as "NE/CNWKSWK" or footage from lines C SE/4  
Lease Owner ROBERT J. BEAMS  
Lease Name R.M. BURCHFIELD Well No. 1  
Office Address 1202 GULF STATES BLDG., DALLAS, TEXAS  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed JANUARY 4, 1959  
Application for plugging filed JANUARY 3, (Phone) 1959  
Application for plugging approved JANUARY 3, (Phone) 1959  
Plugging commenced January 3, 1959  
Plugging completed JANUARY 4, 1959  
Reason for abandonment of well or producing formation DRY HOLE



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well M.A. RIVES, GARDEN CITY, KANSAS  
Producing formation NONE Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SAND	WATER	305	360			
BROKEN SAND	"	360	478			
SAND	"	478	509	8 5/8"	1513	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

FILLED HOLE WITH HEAVY ROTARY MUD FROM 5565' TO 700'. SET RUBBER PLUG AT 700' AND DISPLACED 20 SX CEMENT THRU OPEN END DRILL PIPE. FILLED HOLE WITH HEAVY ROTARY MUD FROM TOP OF CEMENT TO 35'. SET RUBBER PLUG AT 35' and FILLED HOLE BACK INTO CELLAR WITH 10 SX CEMENT. PLUGGING COMPLETED.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 9 1959 1-9-59

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor HELLAR DRILLING CO.  
Address 1014 UNION CENTER BUILDING, WICHITA, KANSAS

STATE OF TEXAS, COUNTY OF DALLAS, ss.  
ROBERT J. BEAMS (employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert J. Beams  
1202 Gulf States Bldg Dallas, Texas (Address)

SUBSCRIBED AND SWORN TO before me this 8th day of January, 1959  
Marie Angven Greene Notary Public.

My commission expires June, 1959

PLUGGING  
FILE SEC 30 T 29 R 42W  
BOOK PAGE 10 LINE 20

CONTRACTOR'S WELL LOG

COMPANY:  
 CONTRACTOR:  
 FARM:  
 LOCATION:  
 COMMENCED:  
 COMPLETED:  
 SURFACE CASING:

R. J. Beams  
 Musgrove Petroleum Corporation  
 Burchfield #1  
 C SE/4 Sec. 30-29-42W  
 Stanton County, Kansas  
 November 29, 1958  
 January 4, 1959  
 8 5/8" Set at 1541'

0	1541	Surface Hole
1541	1990	Shale & Shells
1990	2270	Shale & Lime
2270	2440	Red Bed & Lime Shells
2440	2620	Shale & Shells
2620	2710	Shale & Lime
2710	3025	Lime & Shale
3025	3165	Shale & Lime
3165	3370	Lime & Shale
3370	3510	Lime
3510	3575	Lime & Chert
3575	3895	Lime
3895	3920	Chalky Lime
3920	3960	Lime
3960	3967	Chalky Lime
3967	4230	Lime
4230	4258	Sand
4258	4335	Sandy Lime
4335	4425	Lime
4425	4450	Sandy Lime
4450	4487	Chalky Lime
4487	4560	Lime & Shale
4560	4675	Lime
4675	4697	Lime & Shale
4697	4790	Lime
4790	4845	Sandy Lime
4845	4885	Lime
4885	4930	Lime & Shale
4930	4985	Shale & Lime
4985	5175	Lime & Shale
5175	5265	Shale
5265	5350	Shale & Lime
5350	5376	Sand
5376	5415	Lime & Shale
5415	5460	Sandy Lime
5460	5515	Lime
5515	5540	Mississippi Lime
5540	5565	Lime
	5565	Total Depth

RECEIVED  
 STATE CORPORATION COMMISSION  
 JAN 9 1959  
 CONSERVATION DIVISION  
 Wichita, Kansas

1-9-59

STATE OF KANSAS )  
 COUNTY OF SEDGWICK ) SS

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the log of the BURCHFIELD #1, C SE/4 of Section 30-29-42W, Stanton County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

BY Emil E. Bowers  
 Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 7th day of January, 1959.

Jack Jaye Neff  
 Notary Public

My commission expires June 16, 1959.

PLUGGING  
 FILE SEC. 30 T29 R42W  
 BOOK PAGE 10 LINE 20