


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Stanton County. Sec. 22 Twp. 29-S Rge. (E) 42 (W)
Location as "NE/CNW/SW" or footage from lines Center NE 1/4
Lease Owner Coronet Oil Company
Lease Name Troutman "22" Well No. 1
Office Address P. O. Box 188, Odessa, Texas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 11 1957
Application for plugging filed April 11 (Telephone) 1957
Application for plugging approved April 11 (Telephone) 1957
Plugging commenced April 11 1957
Plugging completed April 11 1957
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes Telephone Conversation with

Name of Conservation Agent who supervised plugging of this well Merle Rives - Pratt, Kansas
Producing formation None Depth to top Bottom Total Depth of Well 5735 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Le Compton	Possible Water	3548	3600	8 5/8"	1588	None
Marmaton	Possible Water	4510	4576			
Morrow Sand	Possible Water	5504	5520			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Cement pumped into hole through Drill Pipe.
7 7/8" Rotary hole filled with mud, weight 9.3#, viscosity 57, from 5735 to 650
Cement 650 to 538
Mud 538 to 35
Cement 35 to Cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Oil Well Cementing Company and R. W. Rine Drilling Co.
Address Elkhart, Kansas and Wichita, Kansas

STATE OF TEXAS, COUNTY OF ECTOR, ss.
O. W. Randolph (employee of owner) ~~xxxxxxx~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) O. W. Randolph
P. O. Box 188, Odessa, Texas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of April, 1957

My commission expires June 1, 1957
Pauline Scannell Notary Public.
County of ECTOR State of Texas

PLUGGING
FILE SEC 22 T. 29 R. 42 W
BOOK PAGE 6 LINE 1

RECEIVED
STATE CORPORATION COMMISSION
APR 17 1957
4-17-57
CONSERVATION DIVISION
Wichita, Kansas

CORONET OIL COMPANY - TROUTMAN "22" Well No. 1

TROUTMAN WELL NO. 1

Ctr. NE/4 15-187-00037-0000
 Sec. 22-29S-42W
 Stanton County, Kansas

CONTRACTOR: The R. W. Rine Drilling Co.

STARTED: March 19, 1957

COMPLETED: April 12, 1957

L O G

Surface Clay	0	-	105	
Blue Shale	105	-	530	Syfo @ 315' 1°
Red Bed	530	-	642	Syfo @ 625' 1°
Gyp	642	-	816	Syfo @ 840' 1/4°
Shale	816	-	945	
Shale & Gyp	945	-	1185	Syfo @ 1100' 1/4°
Shale & Anhydrite	1185	-	1589	Syfo @ 1270' 1° @ 1589' 1°
Shale, Anhydrite & Red Bed	1589	-	1775	8-5/8" csg. @ 1588' w/ 600 sx.
Red Bed	1775	-	2114	Syfo @ 1895' 1/4°
Red Bed & Shale	2114	-	2325	Syfo @ 2270' 1°
Lime & Shale	2325	-	3120	Syfo @ 2625' 1/4°
Lime	3120	-	3281	Syfo @ 3275' 3/4°
Lime & Chert	3281	-	3381	
Lime	3381	-	3623	
Lime & Shale	3623	-	3698	Syfo @ 3625' 3/4°
Lime	3698	-	4360	Syfo @ 4065' 1°
Lime & Shale	4360	-	4510	Syfo @ 4225' 1°
Lime	4510	-	4813	Syfo @ 4790' 1-3/4°
Lime & Chert	4813	-	4920	
Lime	4920	-	4960	Syfo @ 4930' 2°
Lime & Shale	4960	-	5205	
Shale w/ Lime Streaks	5205	-	5340	
Shale	5340	-	5428	Syfo @ 5420' 3/4°
Lime & Sand	5428	-	5460	
Sand & Lime	5460	-	5525	
Sand & Shale	5525	-	5560	
Lime	5560	-	5735	Syfo @ 5585' 3° @ 5670' 3°
				Syfo @ 5725' 2-3/4°
Rotary total depth			5735	D & A

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

RECEIVED
 STATE CORPORATION COMMISSION

APR 22 1957 4-22-57

I, R. M. Green, do hereby certify that the above is a true and accurate log of the Troutman Well No. 1, located Ctr. NE/4, Sec. 22-29S-42W, Stanton County, Kansas.

R. M. Green
 Ass't Secretary and Treasurer

Subscribed and sworn to before me this 17th day of April, 1957.

Charlene Barbour
 Notary Public

My Commission Expires: July 28, 1958

PLUGGING
 FILE SEC. 22 T. 29 R. 42W
 BOOK PAGE 6 LINE 1