

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Stanton

County, Sec. 28 Twp. 29 Rge. 43 (W)

Location as "NE/CNW/SW" or footage from lines 4620' N of SL, 330' E. of WL.

Lease Owner Anderson-Prichard Oil Corp.

Lease Name Stewart "E" Unit Well No. 1

Office Address Box 142, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 2, 1957

Application for plugging filed 3/2 Verbal 3/19 Written 1957

Application for plugging approved 3/2 Verbal 3/4 Written 1957

Plugging commenced 3/2 1957

Plugging completed 3/2 1957

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well S. S. Greider

Producing formation Depth to top Bottom Total Depth of Well 5554' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8" OD	1594'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

RTD 5554'

5554-4954 Heavy Mud

4954-4806 40 Ex. Cement

4806- 37' Heavy mud

37' - 0 1/2 sack Halls, Halliburton plug and 30 sacks cement. Cap on top.

RECEIVED
STATE CORPORATION COMMISSION

MAR 20 1957

CONSERVATION DIVISION
Wichita, Kansas

3-20-57

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Moutray Drilling Company

Address Ponca City, Oklahoma

STATE OF Kansas, COUNTY OF Barton, ss.

J. O. McGinnis

(employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. McGinnis

Box 142, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 19 day of March, 1957

Verdella M. Hankins

Notary Public.

My commission expires December 4, 1958

PLUGGING
FILE SEC 28 T 29 R 43W
BOOK PAGE 144 LINE 40

OWNER: ANDERSON-PRICHARD OIL CORPORATION ET AL. 15-187-00035-0000
CONTRACTOR: MOUTRAY DRILLING COMPANY

ROTARY DRILLING EQUIPMENT
MOUTRAY DRILLING COMPANY

INCORPORATED
WALDO W. MOUTRAY, PRESIDENT
BOX 1904 PHONE 4-5509

ABILENE, TEXAS

DRILLERS LOG ON STEWART E. UNIT # I
NW NE, Sec. 28-29-43W, Stanton, County, Kansas

0 - 50	sand
50 - 395	shale and sand
395 - 618	shale, sand, and lime
618 - 728	shale, sand, and anhydride
728 - 970	shale and red bed
970 - 1116	red bed
1116 - 1227	lime
1227 - 1253	shale and lime
1253 - 1342	shale, red bed, and sand
1342 - 1478	shale and red bed
1478 - 1492	lime
1492 - 1618	shale and lime
1618 - 1748	sand and shale
1748 - 1976	shale and anhydride
1976 - 1995	shale and lime
1995 - 2086	shale and sand
2086 - 2228	shale
2228 - 2454	shale and lime
2454 - 2565	shale
2565 - 2616	lime and shale
2616 - 2673	lime
2673 - 2686	shale
2686 - 2756	lime and shale
2756 - 2774	lime
2774 - 2999	lime and shale
2999 - 3016	lime
3016 - 3287	shale and lime
3287 - 3328	lime
3328 - 3424	shale and lime
3424 - 3464	lime
3464 - 3507	shale
3507 - 3553	lime
3553 - 3616	shale and lime
3616 - 3684	lime
3684 - 3967	shale and lime
3967 - 3995	shale
3995 - 4233	lime
4233 - 4298	shale and lime
4298 - 4314	sand
4314 - 4320	shale and lime
4320 - 4338	lime

PLUGGING
FILE SEC. 28 T. 29 R. 43W
BOOK PAGE 144 LINE 40

FILED
COMMISSIONER
4-4-57
APR 4 - 1957
CON. DIVISION
Kansas

ROTARY DRILLING EQUIPMENT
MOUTRAY DRILLING COMPANY

INCORPORATED

WALDO W. MOUTRAY, PRESIDENT
BOX 1904 PHONE 4-5509

ABILENE, TEXAS

Drillers Log on Stewart E. Unit # I:

4338 - 4666	shale and lime
4666 - 4754	lime
4754 - 4772	shale and lime
4772 - 4778	shale
4778 - 4926	shale and lime
4926 - 4980	shale
4980 - 5017	shale and lime
5017 - 5057	shale
5057 - 5078	shale and lime
5078 - 5240	shale
5240 - 5307	lime and shale
5307 - 5321	shale
5321 - 5352	lime and sand
5352 - 5406	shale, sand, and lime
5406 - 5469	lime
5469 - 5475	shale and lime
5475 - 5561	lime -- TD

PLUGGING

FILE SEC 28 T 29 R 43w
BOOK PAGE 144 LINE 40

4-4-57 DIVISION

APR 4 - 1957

CONSERVATION DIVISION
Wichita, Kansas

Waldo W. Moutray
Waldo W. Moutray

Subscribed before me this 3rd day of April 1957
Ira Rowe - Notary Public
My Commission Expires May 6 - 1958