

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 19 1976
1-19-76
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Texas Inc.
 Complete Address Box 2420, Tulsa, Okla. 74102
 Lease Name Fall Creek Unit, Tract 2 Well No. 8
 Location SE NW SW Sec. 3 Twp. 35 Rge. 3 (W)
 County Sumner Total Depth 5159
 Abandoned Oil Well Gas Well ^{WATER SUPPLY} ~~Input~~ Well SWD Well D & A
 Other well as hereafter indicated Water Supply Well
 Plugging Contractor Clark's Well Servicing
 Address Medicine Lodge, Kans. License No. 583
 Operation Completed: Hour 11:00 AM Day 16 Month 1 Year 1976

The above well was plugged as follows: 10 3/4" - 500' - RTD 3315 - Perf. 3315 to 3715'
 Ran in tubing to 2920' - Halliburton Pumped 50
 sacks cement thru tubing, pulled out tubing, let
 set 24 hours. Packed upon 7" found it grouted at
 approximately 1100', took off one joint 7" exp, pumped
 50 sacks thru 7" to approx 1060', filled to approx 920'.
 Packed casing to 300', pumped 50 sacks cement
 thru 7" to 300', filled to approximately 200', pulled
 casing, put bridge at 30' and filled to cellar with 15 sacks
 cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Ernest Leaker
Well Plugging Supervisor

DATE 1/19/76
INV. NO. 9582-E