

15-095-30048-0000

Form CP-3  
Rev. 6-26-62

KANSAS

**STATE CORPORATION COMMISSION**

**CONSERVATION DIVISION AGENT'S REPORT**

**RECEIVED**  
STATE CORPORATION COMMISSION

**JUN 20 1966**

**CONSERVATION DIVISION**  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Graybol Oil Corporation

Complete Address: 2200 National Bank of Tulsa Bldg., Tulsa, Oklahoma

Lease Name Simon Well No. # 1

Location C SE SE Sec. 21 Twp. 29 Rge. 10 (E) (W) W

County Kingman Total Depth 4606'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A   X  

Other well as hereafter indicated:       

Plugging Contractor: Graybol Oil Corporation

Address: 2200 National Bank of Tulsa, Tulsa, Oklahoma License No.       

Operation Completed: Hour 8:15AM Day 13th Month June Year 1966

The Above well was plugged as follows:

251' of 8 5/8" surface pipe, cement circulated with 175 sacks. Hole  
was filled with drilling mud to 250', 1st cementing plug, bridged with  
2 sacks of dry cement and 1/2 sack of hulls on fluid at 250', and cemented  
with 23 sacks. Hole was filled with drilling mud to 40', 2nd cementing  
plug bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at  
40', and cemented with 9 sack to the base of the cellar. Rat hole bridged  
and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

DATE 6/20/66  
INV. NO. 3415-u

Signed: Archie Elving  
Well Plugging Supervisor