

R  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Stevens

Location: 330 ft. of 55/4 Sec. 33 Twp. 32 Rge. 35 (E) (W) W

Name of Field: \_\_\_\_\_ Total Depth: 2773'

I have this date completed supervision of plugging of:

Lease Name: DeCamp Well No. ~~2773~~ 1

Operator's Full Name: Worthen Natural Gas Producing Co.

Complete Address: 502 Rele Bldg, Wichita, Kans.

Plugging Contractor: \_\_\_\_\_

Address: \_\_\_\_\_ License No. \_\_\_\_\_

Oil Well  Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 1:30 pm Day 24 Month January Year 1960

The above well was plugged as follows:

10 3/4" - 631' 2646' of 7" 143' of 5 1/2" liner. <sup>Bottom</sup> Top of  
liner set at 2773' 25 sacks cement pumped on bottom  
through tubing. Top of cement at 2636' 800' of  
2" pulled. Hole was filled with mud to 560' Rock  
bed set by 560' to 550' 30 sacks cement pumped on  
bed. Hole mud to 30' Rock bed to 30'  
10 sacks cement poured to base of collar.

Signed: [Signature]  
Conservation Division Agent

Reviewed: [Signature]  
Field Supervisor

Remarks: \_\_\_\_\_

INVOICED  
DATE 2/9/60  
INV. NO. 944-W