

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

2-15-65

FEB 15 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Panhandle Eastern Pipe Line Co.

Complete Address: Box 828 Liberal, Kansas

Lease Name Howell-Rinehart Well No. # 1-23

Location C NE Sec. 23 Twp. 32 Rge. 39 (E) (W)

County Stevens Total Depth 2712'

Abandoned Oil Well      Gas Well       Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Sargent Casing Pulling Service

Address: Liberal, Kansas License No. 511

Operation Completed: Hour 4 PM Day 12 Month 2 Year 65

The Above well was plugged as follows:

16"-571' Circulated w/cement. 10 3/4"-1620' Circulated w/cement. 7"-2350' Cemented.

Plug back to 2510' Plug bottom w/70 Sax. cement top cement 2000'

Mud 2000' to 1804' Spotted 50 Sax. cement 1804' to 1604'

Mud 1604' to 590' Spotted 50 Sax. cement 590' to 500'

Mud 500' to 30' Sand 30' to 20' 10 Sax. cement 20' to 0

Pulled 1597" 7" pipe. Company Pump. No 10 3/4" pipe pulled.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/15/65  
INV. NO. 685-W

Signed: [Signature]  
Well Plugging Supervisor