

15-189-10182-0000

Form CP-3  
Rev. 6-26-62

70  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 22 1964  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Anadarko Production Company

Complete Address: Box 351, Liberal, Kansas

Lease Name Armstrong "B" Well No. # 1

Location C NW Sec. 25 Twp. 32 Rge. 39 (E) (W) W

County Stevens Total Depth 3026

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Sargent Casing Pulling Service

Address: 121 West 9th St., Liberal, Kansas License No. 511

Operation Completed: Hour 12:00PM Day 20th Month Dec. Year 1964

The Above well was plugged as follows:

612' of 8 5/8" surface pipe, cemented with 400 sacks. 3024' of 4 1/2" long  
string, cemented with 225 sacks. Temperature survey 2100'. Top perforation  
2856'. 35 sacks of cement was pumped in 4 1/2", cement and plug was pumped to  
2500'. At 650' 25 sacks of Gel-Mud and 35 sacks of cement was pumped into  
4 1/2", bringing the top of the cement to 556'. Hole was filled with mud to  
45', bridge plug set at 45', and cemented with 15 sacks to the base of the  
cellar.

2052' of 4 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

DATE 12/23/64

INV. NO. 391-10

Signed: Archie Elving  
Well Plugging Supervisor