

TYPE

AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

Compt. _____

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

F Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

C Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238. No Log

LICENSE # 6712EXPIRATION DATE 6/30/83OPERATOR Martell Oil CompanyAPI NO. On file at KCC officeADDRESS Box 184COUNTY GreenwoodHamilton, Kansas 66853FIELD Wiggins** CONTACT PERSON Henry MartellPROD. FORMATION CattlemanPHONE 316-678-3643PURCHASER No oil sold from this leaseLEASE Wiggins "B"

ADDRESS _____

WELL NO. 3

WELL LOCATION _____

DRILLING Kelly Down Drilling Co.500 Ft. from West Line and

CONTRACTOR _____

ADDRESS Neosho Falls, Kansas 66758250 Ft. from South Line of NW of
the SW (Qtr.) SEC 29 TWP 24 RGE 11 KKK

PLUGGING _____

WELL PLAT

(Office
Use Only)

CONTRACTOR _____

ADDRESS _____

KCC _____

KGS _____

SWD/REP _____

PLG. _____

TOTAL DEPTH 1780

PBTD _____

SPUD DATE _____

DATE COMPLETED _____

ELEV. GR 1110

DF _____

KB _____

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE _____

Amount of surface pipe set and cemented 100-7" DV Tool Used? _____THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other _____

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

_____, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

(Name)

SUBSCRIBED AND SWORN TO BEFORE ME this _____ day of _____

19 _____

(NOTARY PUBLIC)

MY COMMISSION EXPIRES: _____

** The person who can be reached by phone regarding any questions concerning this information.

AUG 25 1983

Wichita, Kansas

OPERATOR Martell Oil Co.

LEASE Wiggins "B"

SEC. 29 TWP. 24 RGE. 11

FILL IN WELL INFORMATION AS REQUIRED:

WELL NO. 3 "B"

FORMATION DESCRIPTION, CONTENTS, ETC.		TOP	BOTTOM	NAME	DEPTH
* Check if no Drill Stem Tests Run.					
Soil & clay	22			Gamma ray	1100 to
Shale	59			neutron log	1759
Lime	191			copy enclosed	
Shale w/lime strks	1005				
Shale	1145				
Lime	1325				
Shale	1445				
Lime	1485				
Shale & lime	1620				
Shale	1702				
Lime	1710				
Shale	1733				
Sand	1744				
Shale	1780				
RTD	1780				

If additional space is needed use Page 2, Side 2

Report of all strings set—surface, intermediate, production, etc. CASING RECORD (New) or (XXX)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	10"	7"	20#	102	Regular	35	Cal. Cl. 100#
long string	6 1/2"	4 1/2"	9.5	1770	Pozmix	50	Salt 100#
(production)					Invoices enclosed		

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			1-10 holes	3 1/2 V Ji	1745 to 1736
			Invoice enclosed		

TUBING RECORD

Size	Setting depth	Packer set at
2 3/8	1760	None

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acid 250 gal. 15% Hcl. Frac-5000# 20-40 Sand	1745 to 1736
10000# 12-20 Sand	Invoice enclosed
12000 8-16 Sand	

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity
None	Pumping	36
Estimated Production - I.P. Approx. Trace bbls.	Gas MCF 80 %	Gas-oil ratio Appro 1 bbls.
Disposition of gas (vented, used on lease or sold)	Perforations	CFPB