

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

JUN 3 1963

6-3-63

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Davidor & Davidor Inc.

Complete Address: 4515 N. Santa Fe, Oklahoma City, Oklahoma

Lease Name Stucky Well No. # 1

Location SE SE SW Sec. 21 Twp. 29 Rge. 6 (E) (W) W

County Kingman Total Depth 4599

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: J. C. Wood Casing Puller

Address: Box 65, Edmond, Oklahoma License No. 533

Operation Completed: Hour 12:00PM Day 30th Month May Year 1963

The Above well was plugged as follows:

240' of 8 5/8" surface pipe, cement circulated with 115 sacks. 4599' of  
4 1/2" long string, cemented with 250 sacks. Plug was pushed to 3600',  
cemented with 5 sacks. Hole was filled with mud to 240', 10' rock bridge,  
cemented with 25 sacks. Hole filled to 25', 10 rock bridge, cemented  
with 5 sacks to base cellar.

3134' of 4 1/2" long string recovered from hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/4/63

INV. NO. 9188-14

Signed: Arlene Elving  
Well Plugging Supervisor