

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name National Oil Co.

Complete Address 200 W. Douglas, Suite <sup>800</sup>~~550~~, Wichita, Ks. 67202

Lease Name Tonn Well No. 1

Location NE SW SE Sec. 26 Twp. 29s Rge. 6 (E) (W) X

County Kingman Total Depth 4518

Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Casing Pulling.

Address Box 176, Chase, Ks. 67524 License No. 683

Operation Completed: Hour 12 N. Day 29 Month 8 Year 1980

The above well was plugged as follows:

315' 8 5/8" casing. 4 1/2" casing set at 4287' w/150 sax cement. Pref's  
at 4144 to 47'-Allied mixed & pumped 35 sax common cement in 4 1/2"  
casing to 3640'-Pull 3300' casing-Allied mixed & pumped 8 sax hulls  
25 sax gel-125 sax 50/50 posmix cement w/4% gel & 3% cc to top of  
casing. Shut in w/400# pressure.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP - 2 1980

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 9-4-80  
INV. NO. 3004W

Signed: [Signature]  
Well Plugging Supervisor  
CONSERVATION DIVISION  
Wichita, Kansas