

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name National Oil Co.

Complete Address 200 W. Douglas, Suite 800, Wichita, Ks. 67202

Lease Name Tonn Well No. 2

Location SE NW SE Sec. 26 Twp 29S Rge. 6 (E) (W) X

County Kingman Total Depth 4140

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

~~X~~ ~~XXXXXXXXXXXXXXXXXXXXXXXXXXXX~~ Depth of well is 4140' not 4126'.

Plugging Contractor Kelso Casing Pulling.

Address Box 176, Chase, Ks. 67524 License No. 683

Operation Completed: Hour 10:30 Am. Day 29 Month 8 Year 1980

The above well was plugged as follows:

340' 8 5/8" casing w/200 sax cement. 4 1/2" casing set at 4125' w/150  
sax cement. Open hole. Sand back to 4100'-Top sand w/4 sax mixed  
cement w/ dump bailer. Pull 3505' casing. Allied mixed & pumped  
8 sax hulls-25 sax gel-125 sax 50/50 posmix cement w/4% gel & 3%  
cc to top of casing. Shut in w/200# pressure.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP - 2 1980  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED  
DATE 9-4-80  
INV. NO. 3003-W