

40
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 4 1964
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212. North Market
Wichita 2, Kansas

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 Fourth National Bank Bldg., Wichita, Kansas

Lease Name Ravenstein "A" Well No. # 1

Location C NW NW Sec. 26 Twp. 29 Rgs. 6 (E) (W)W

County Kingman Total Depth 4561

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Pickrell Drilling Company

Address: 705 Fourth National Bank Bldg., Wichita, Ks License No.

Operation Completed: Hour 2:30PM Day 2nd Month Nov. Year 1964

The Above well was plugged as follows:

200' of 8 5/8" surface pipe, cement circulated with 155 sacks. Hole was
filled with drilling mud to 220', 1st cementing plug, bridged solid with
hulls on fluid at 220', and cemented with 25 sacks. Hole was filled with
drilling mud to 40', 2nd cementing plug, bridged solid with hulls on
fluid at 40', and cemented with 10 sacks to the base of the cellar.
Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 11/4/64

INV. NO. 110-42