

15-095-21154-0000

KANSAS

FORM CP-3  
Rev. 10-8-81

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15- none ✓

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Pickrell Drilling Co.

Complete Address Litwin Bldg. , Ste.205, Wichita, Kansas 67202

Lease Name Ruth "A" Well No. 1

Location W/2 NW SW Sec 27 Twp. 29 Rge. 6W (East)(West)

County Kingman Total Depth 4437'

Abandoned Oil Well XX Gas Well      Input Well      SWD Well      D&A     

Other well as hereinafter indicated     

Plugging Contractor Clarke Corporation

Address 107 W. Fowler, Medicine Lodge, Kansas 67104 License No. 583

Operation Completed: Hour: 11<sup>00</sup> AM Day: 25 Month: 11 Year: 19 81

Plugging Operations attended by Agent?: All      Part      None     

The above well was plugged as follows:

208' of 8 5/8" SP W/175 sks SIP-500<sup>II</sup>

4 1/2" csg. set @ 4272' W/110 sks

PB to 4247' Top Perf - 4154' to 4163' SB to 4000' & W/4 sks

Pump 15 gel, 6 Hulls, 10 gel, Release plug and displace W/125 sks common  
cement 2% gel 3% C.C. Cemented by Allied

Recovered 3120' of 4 1/2" csg.

11-30-81

RECEIVED  
STATE CORPORATION COMMISSION

I hereby certify that the above plugging instructions were given as herein stated.

INVOICED

Signed: [Signature]  
Conservation Division Agent

DATE 12-17-81  
INV. NO. 8767-W