

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 123--44.

LOCATION Se-NE-NW-

SEC. 9 TWP. 35 RGE. 3West.

Dry Hole Yes Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. One Lease Peter Polivka

Operator The Texas Co. Address Box 1801 Wichita Kansas.

Field Cadwell. County Sumner..

Total Depth 4853 Feet. 600 Ft 10/4" Surface pipe Cemented in with 450 seaks Cemnet.

(Describe briefly the manner in which the well was plugged)

Heavy mud pumped in from bottom 4835 up to 600ft or bottom of surface pipe then set bridge and plug filling up to 550 ft usein 25 sacks Cemnet
then mudded to 30 ft then then bridgeed useing 10 sacks cement welded steel cap on top of surface pipe with W/1# gate

RECEIVED
STATE CORPORATION COMMISSION
NOV 16 1951
CONSERVATION DIVISION
Wichita, Kansas

W. S. Buffington
District Conservation Agent

Date Nov 14--51...

PLUGGING
FILE SEC 9-T-35 R-30
BOOK PAGE 12 LINE 44