

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

#2

API NUMBER 15-095-20964-0000

LEASE NAME Whitelaw

WELL NUMBER #1

SPOT LOCATIONS S/2, NW, SW

SEC. 14 TWP. 29S RGE. 7 (XXX(W))

COUNTY Kingman

Date Well Completed 5-27-81

Plugging Commenced 2-26-88

Plugging Completed 3-1-88

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Robert F. White

ADDRESS 2400 N. Woodlawn, Suite 114, Wichita, KS 67220

PHONE # (316) 688-1616 OPERATORS LICENSE NO. 5061

Character of Well Oil & Water  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District 2 Office

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? yes

Producing formation Viola Depth to top 4486' bottom 4489' T.D. 4489'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface	water	-0-	254'	8 5/8"	254'	-0-
Viola	oil & water	-0-	4486'	4 1/2"	4486'	3337'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Built sand plug from 4489' to 4335'. Ran cement plug 4330' to 4300' (4 sax) by bailer and sand line. Shot pipe at 3337' and pulled. Baled hole to 370', set plug at 350'. Bridged with sacks & dirt to 300'. Used 5 yds Redi-mix to fill surface pipe.

(If additional description is necessary, use BACK of this form)

Name of Plugging Contractor Great Bend Casing Pullers, Inc.

Address Box 768, Great Bend, Kansas 67530

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAR 10 1988  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

STATE OF Kansas COUNTY OF Sedgwick, ss.


Robert F. White \_\_\_\_\_ or  
 (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Robert F. White

(Address) 2400 N. Woodlawn, Wichita, KS

SUBSCRIBED AND SWORN TO before me this 9 day of March, 1988

Carol Pick  
 Notary Public



My Commission expires: Sept. 20, 1990

Carol Pick