

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-095-20975-0000

LEASE NAME Whitelaw

WELL NUMBER 2

SPOT LOCATION N/2 SW/4 SW/4

SEC. 14 TWP. 29 SRGE. 7 ~~XXXX~~(W)

COUNTY Kingman

Date Well Completed 8-2-80

Plugging Commenced \_\_\_\_\_

Plugging Completed \_\_\_\_\_

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Robert F. White

ADDRESS 505 Union Center

PHONE # (316) 26307957 OPERATORS LICENSE NO. 5061

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District 1 Office - Warren Kirkpatrick

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation Viola Depth to top 4481' bottom 4485' T.D. 4485'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface	Water	0	254'	8 5/8"	254'	-0-
Viola Lime	Viola - oil & water	0	4483'	4 1/2"	4483'	3140'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugged back from T.D. of 4485' to 4350' with 100 gallons sand and 4 sack cement on top. Shot 4 1/2" casing off at 3140'. Pulled 3140' of 4 1/2". Built bridge @ 350' up to 300'. Fill hole and surface casing with Redi-mix to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pulling Service License No. \_\_\_\_\_  
Address Box 768, Great Bend, Kansas 67530

RECEIVED  
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Sedgwick, ss.


MAY 21 1987

Robert F. White (operator) of above-described well, being first duly sworn on oath, says: I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 505 Union Center, Wichita, KS

SUBSCRIBED AND SWORN TO before me this 19 day of May, 1987



Carol Pick  
Notary Public

My Commission expires: Sept. 20, 1990

cc: Great Bend Casing PULLING Service