

LEASE NAME Komarek "A"

WELL NUMBER #2

3300 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 11 TWP. 29S RGE. 10 (E) or (W)

COUNTY Kingman

Date Well Completed _____

Plugging Commenced 11-5-93

Plugging Completed 11-5-93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Gore Oil Company

ADDRESS P.O. Box 2757

PHONE#(316) 263-3535 OPERATORS LICENSE NO. 5552

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-29-93 (date)

by Jack Luthi (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? See CP-1

Producing Formation Indian Cave Depth to Top 2527' Bottom 2534' T.D. 2620'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Indian Cave	Gas, Water	0	259'	8 5/8"	259'	0'
		0	2618'	4 1/2"	2618'	1400'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Plug back with sand to 2475'. Dump 4 sx cement. Stretch, rip 4 1/2" at 1900'. Spot 35 sx 60/40; 4% Gel at 1435'. Spot 35 sx 60/40, 4% Gel at 987'. Circulated cement to surface from 322'. Hole remained full. Plugging complete.

Name of Plugging Contractor Allied License No. _____

Address Medicine Lodge, KS. 67104


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Gore Oil Company

STATE OF Kansas COUNTY OF Sedgwick, ss.

Scott W Scheuerman (Employee of Operator) ~~Operator~~
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Scott W Scheuerman

(Address) P.O. Box 2757, Wichita, KS 67201-2757



SUBSCRIBED AND SWORN TO before me this 29th day of November, 19 93

Rebecca K. Crawford
Notary Public

My Commission Expires: January 7, 1995

USE ONLY ONE SIDE OF EACH FORM

RECEIVED
STATE CORPORATION COMMISSION
Form CP-4
Revised 05-88

NOV 30 1993

CONSERVATION DIVISION
Wichita, Kansas