

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-06721110-0000

LEASE NAME Johnson

RECEIVED
KANSAS CORP. COM.

1999 JUN 22 2:11:05

1-28-99

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER I-31

4950 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 31 TWP. 29S RGE. 38 (E) or W

COUNTY Grant

Date Well Completed 1/31/91

Plugging Commenced 1/5/99

Plugging Completed 1/7/99

LEASE OPERATOR Harris Oil and Gas Company

ADDRESS 1125 17th Street, Suite 2290 Denver, CO 80202

PHONE# (303) 293-8838 OPERATORS LICENSE NO. 9953

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1/5/99 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filled? Yes If not, Is well log attached? N/A

Producing Formation St. Louis Depth to Top 5656 Bottom 5672 T.D. 5800

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	1769	--
				5 1/2	5793	1314

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each section.
Mixed 4 sx hulls & 25 sx cement to plug perfs from 5655 to 5455, pumped mud to 1800, then mixed 25 sx cement plug in 5 1/2 from 1800 to 1600, recovered 1314 5 1/2. Mixed 40 sx plug from 600 to 500, 10 sx plug from 40 to 0. Cut off & capped 8 5/8 3 ft below G.L.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent and Horton Plugging, Inc. License No. 31151

Address Route 2, Box 49BA Tyrone, OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Harris Oil and Gas Company

STATE OF Colorado COUNTY OF Denver, ss.

Doug Hoisington (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 1125 17th Street, Suite 2290 Denver, CO 80202

SUBSCRIBED AND SWORN TO before me this 25 day of January, 19 99

Jimmy L. Adams
Notary Public

My Commission Expires: March 31, 2001