

15-095-01029-000 ①

RECEIVED
STATE CORPORATION COMMISSION

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

SEP 2 1982

CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Kingman SEC. 16 TWP. 29S RGE. 9W E/W
Location as in quarters or footage from lines:
NE SE NE

Locate Well
correctly on above
Section Platt.

Lease Owner A. Scott Ritchie
Lease Name Miller A #1 Well No. _____
Office Address Suite 950 125 N. Market Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 8-6-82
Plugging completed 8-12-82
Reason for abandonment of well or producing formation Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie

Producing formation _____ Depth to top _____ bottom _____ T.D. 4462'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	200'	none
				5-1/2"	4460'	1772'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Pumped bottom with 50 sacks cement to 4100'. Shot casing @3519', 3227', 2927', Allied
pumped 77 sacks gel down 5-1/2", shot casing @2606', 2309', 2011', 1812', pulled a total
of 54 joints of 5-1/2" casing. Plugged well with 15 sacks gel, 6 sacks hulls, 10 sacks
gel and 125 sacks common cement.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347 Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of August, 19 82



My Commission expires:

Irene Hoover
Notary Public.

DRILLERS LOG
A. SCOTT HIGHTON
#1 HILLER A
APP. NE SE 1/4, SEC. 16-09-01
Kingman County, Kansas

Contractor - M.S.T. Drilling Company, Inc.

Commenced: 11/15/63
Completed: 12/14/63
Elevation: 1646 D.F.

From	To	Description	Remarks
0	125	Surface clay & sand	
125	500	Red Beds	
500	855	Shells and shale	200' 8-5/8" Surf. Ceg. w/125 Sacks cement
855	880	Anhydrite	
880	1230	Shells and shale	1460' 5-1/2" Ceg. w/100 Sacks Salt Saturated Cement
1230	1330	Salt & Shale	
1330	1350	Shells and shale	25/c Gal.
1350	1400	Lime	
1400	1460	Lime & Shale	
1460	1495	Lime	
1495	1780	Lime & Shale	
1780	2065	Lime	
2065	3215	Shale & Lime	
3215	3321	Lime	
3321	3728	Lime & Shale	
3728	4116	Lime	
4116	4168	Lime & Shale	
4168	4210	Chert	
4210	4310	Lime	
4310	4462	Lime & Shale	
4462		Total Depth	

I certify to the best of my knowledge and belief, the above represents a true and accurate Drillers Log record of the captioned well.


James E. Thompson
James E. Thompson

STATE OF KANSAS)
COUNTY OF SHAWNEE) SS:

Subscribed and sworn to before me this 19th day of December, 1963.

Janifer Wallace
Janifer Wallace, Notary Public

My Commission Expires: April 17, 1966



RECEIVED
STATE CORPORATION COMMISSION
MAY 13 1962
CONSERVATOR OF PUBLIC MONUMENTS
WICHITA, KANSAS