


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kingman County, Sec. 17 Twp. 29 Rge. 9 (E) W (W)
Location as "NE/CNW/SW" or footage from lines Cen. SE SE SE
Lease Owner: Cities Service Oil Company
Lease Name: Schreiner Well No. 1
Office Address: Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 31, 19 55
Application for plugging filed January 31, 19 55
Application for plugging approved January 31, 19 55
Plugging commenced January 31, 19 55
Plugging completed January 31, 19 55
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation Arbuckle Depth to top 4640 Bottom Total Depth of Well 4670 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	320'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

4670-250', heavy mud.
250-205', wood plug, rock bridge and 15 sacks cement.
205-25', mud.
25' to base of cellar, wood plug and 5 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Prime Drilling Company
Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
V. M. Conover (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V.M. Conover
Box 751, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of February, 19 55

W.D. Smith
Notary Public.

My commission expires March 12, 1955.

PLUGGING
FILE REC 177 29 R 9W
BOOK PAGE 94 LINE 36

2-16-55
WICHITA, KANSAS

WELL RECORD

Company Cities Service Oil Co. Well No. 1 Farm Schreiner
 Location 330' North and 330' West of NE Cor. Sec. 17 T. 29 R. 9W
 Elevation 1661 (1658 Cr.) County Kingman State Kansas
 Drlg. Comm. January 14, 1955 Contractor Price Drilling Company
 Drlg. Comp. January 31, 1955 Acid None
 T. D. 4670' Initial Prod. Dry Hole - Plugged and Abandoned Feb. 1, 1955

CASING RECORD:

8-5/8" @ 320' cas. with 225' ex.

FORMATION RECORD:

clay & sand shale	0-60
red bed & shale	60-850
shale & shells	1400
anhydrite	1440
lime	2000
lime & shale	2495
shale & lime	2710
lime & shale	2890
lime	3440
lime & shale	3690
lime	4115
lime & shale	4190
chert & lime	4250
lime	4275
lime & shale	4475
lime & chert	4605
lime	4540
sand & shale	4540
lime	4670 T. B.

Topoka	2950'
Douglas	3395'
Lanning	3525'
Miscellaneous	4185'
Hindarhook	4279'
Viola	4475'
Simpson	4534'
Arbuckle	4640'
Penetration	90'
Total Depth	4670'

D. S. T. 4190-4200, open 30 mins., rec. 25' mud; D. H. P. 3900/30 mins.

D. S. T. 4202-20, open 1 hr., rec. 32' mud with few specks oil and 50' muddy salt water; D. H. P. 13250/30 mins.

D. S. T. 4474-80, open 1 hr., rec. 31' mud; D. H. P. failed to record.

D. S. T. 4474-85, open 1 hr., rec. 3160' salt water; D. H. P. 13250/30 mins.

SLOPE TESTS (SUMS ONLY):

500'	3/4°	2000'	1/2°
1000'	0°	3500'	1°
1500'	3/4°	3200'	2-1/2°
2000'	1/2°	4470'	1°
2500'	1/2°		

PLUGGING
 FILE SEC. 17-29-R2W
 BOOK PAGE 94 LINE 34