

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Kingman SEC. 19 TWP. 29S RGE. 9W E/W
Location as in quarters or footage from lines:
NE/4

Lease Owner TXO Production Corp.
Lease Name Huelscamp Well No. 1
Office Address 200 W. Douglas, Suite 300, Wichita Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed October 19, 1983
Application for plugging filed October 20, 1983
Plugging commenced 2:45 a.m. October 19, 1983
Plugging completed 4:45 a.m. October 19, 1983
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Permission was obtained

Name of Conservation Agent who supervised plugging of this well Steve Durant
Producing formation _____ Depth to top _____ bottom _____ T.D. _____
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	8 5/8	0	334'	J-55	8 fts.	

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged well with 150 sks 60-40 pos,
1st, plug 840' 70 sks, 2nd plug 360' 50 sks,
3rd plug 10 sks with rubber plug, 10 sks rat hole
10 sks mouse hole. Job complete 4:45 a.m.
October 19, 1983. State Plugger Steve Durant

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Cementing

STATE OF Kansas COUNTY OF Sedgwick, ss.
Arnie Little (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Arnie Little Arnie Little
453 S. Webb Rd., P.O. Box 18611
Wichita (Address) Kansas 67207

SUBSCRIBED AND SWORN TO before me this 20th day of October, 19 83

My Commission expires: March 20, 1987


Kathleen G. Quinn
Notary Public.

RECEIVED
OCT 24 1983
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

15-095-21371-0000

453 SOUTH WEBB ROAD
P.O. BOX 18611
WICHITA, KANSAS 67207
(316) 685-5372

ALDEBARAN



DRILLING CO. INC.

WELL LOG

WELL NAME: Huelscamp #1

WELL LOCATION: NE/4

Sec. 19-29S-9W

COMMENCED: October 15, 1983

COMPLETED: October 19, 1983

CASING RECORD: _____

8 5/8" casing set @ 334'

OPERATOR: TXO Productions Corp.

CONTRACTOR: Aldebaran Drilling Co. Inc.

FORMATION:

FROM:

TO:

SURFACE SAND	0	132'
RED BED	132'	350'
RED BED - SHALE	350'	1078'
SHALES	1078'	1496'
SHALES WITH LIME STREAKS	1496'	1810'
SHALE AND LIME	1810'	2122'
SHALES	2122'	2250'
SHALES WITH LIME	2250'	2475'
SAND SHALE AND LIME	2475'	2641'

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

I CERTIFY THAT THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S LOG ON THE WELL DRILLED

NE/4 Sec 19-29S-9W, Kingman County, Kansas TO THE BEST OF MY

KNOWLEDGE AND BELIEF.

ALDEBARAN DRILLING CO., INC.

Arnie Little
Arnie Little

SUBSCRIBED AND SWORN TO BEFORE ME THIS 20th DAY OF October, 1983

MY APPOINTMENT EXPIRES: March 20, 1987

Kathleen G. Quinn NOTARY PUBLIC