

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER _____

LEASE NAME Lubbers

WELL NUMBER #1

_____ Ft. from S Section Line

_____ Ft. from E Section Line

C NW NW
SEC. 25 TWP. 29 RGE. 9W (E) or (W)

COUNTY Kingman

Date Well Completed _____

Plugging Commenced 6-14-88

Plugging Completed 6-17-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR D.R. Lauck Oil Co., Inc.

ADDRESS 221 S. Broadway, Suite 400
Wichita, Kansas 67202

PHONE# (316) 263-8267 OPERATORS LICENSE NO. 5427

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #2 Wichita, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4232'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	325'	none
				5-1/2"	4228'	3496'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plugged off bottom with sand to 4150' and 5 sacks cement. Shot pipe @3600', 3496', pulled a total of 105 joints of 5-1/2" casing. Plugged surface with 3 hulls, 20 gel, 1 hull, 8-5/8" plug, 120 cement, 60/40 pos., 2% gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. STATE 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss. 6-27-88

R. Darrell Kelso (Employee of Operator) (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well is true and that the same are true and correct, so help me God.


(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 22nd day of June, 19 88

Jane Hoover
Notary Public

My Commission Expires:



D. R. Lauck Oil Company, Inc. - Lubbers #1
 C NW NW Sec. 25-29S-9W
 Kingman County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.
 301 S. Broadway
 Wichita, Kansas 67202

Commenced: June 18, 1977
 Completed: June 27, 1977

Drillers Log

Sand	40
Sand, Shale & Redbed	325
Red Bed	575
Shale & Shells	1367
Anhydrite	1393
Shale & Shells & Lime Streaks	1600
Shale Shells	1900
Shale & Lime	2315
Shale Shells	2520
Shale & Lime	1945
Shale Shells	3155
Shale & Lime	3695
Shale Shells	3850
Lime	4232 RTD

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 06 1978
 CONSERVATION DIVISION
 Wichita, Kansas