

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kingman County, Sec. 26 Twp. 29S Rge. (E) 9 (W)

Location as "NE/CNW/SW" or footage from lines NW SE SE

Lease Owner Sunray Mid-Continent Oil Company

Lease Name J. F. Cox Well No. 1

Office Address Box 788, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 6 19 59

Application for plugging filed March 9 19 59

Application for plugging approved March 10 19 59

Plugging commenced March 6 19 59

Plugging completed March 6 19 59

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred W. Hampel

Producing formation Depth to top Bottom Total Depth of Well 4353 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	431'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with drilling mud to 431', set 1/3 sack hulls, Halliburton wooden plug and 25 sacks cement, filled hole with drilling mud, 1/3 sacks hulls, Halliburton wooden plug and 15 sacks cement. Cement to surface. Plugging completed.

Well Log attached.

RECEIVED
STATE CORPORATION COMMISSION
MAR 25 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Halliburton Oil Well Cementing Company
Address

STATE OF Kansas COUNTY OF Barton ss.
N. E. Montgomery (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) N. E. Montgomery
Box 788, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of March, 19 59

Notary Public

My commission expires December 24, 1960

PLUGGING
FILE SEC. 26 T. 29 R. 9W
BOOK PAGE 20 LINE 11

Sunray Mid-Continent Oil Company
Tulsa, Oklahoma

Tulsa, Oklahoma
March 13, 1959

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: February 23, 1959
Drilling Completed: March 6, 1959

J.F. Cox #1 C. of NW/4 SE/4
SE/4 of Sec. 26-29S-9W, Spivey
Grabs Field, Kingman Co., Ks.

DRILLERS' LOG

Depth Figures Indicate Base of Formation:

Surface	0
Shale & Sand	40
Shale & Shells	1375
Shale & Lime	1550
Lime & Shale	2110
Shale & Lime	2970
Lime & Shale	3095
Lime	3190
Lime & Shale	3290
Shale Sand & Lime	3460
Shale	3550
Lansing	3560
Lime	4027
Lime & Shale	4145
Lime	4195
Lime & Shale	4255
Miss. Chat	4260
Chat	4315
Lime	4353 TD

RECEIVED
STATE CORPORATION COMMISSION

MAR 25 1959

CONSERVATION DIVISION
Wichita, Kansas

I, Fred E. Stickle hereby certify the above to be a true and complete Drillers Log of Sunray Mid-Continent Oil Company's J.F. Cox #1 C. of NW/4 SE/4 SE/4 of Section 26-29S-9W, Spivey-Grabs Field, Kingman County, Kansas.

Fred E. Stickle
Fred E. Stickle

Lillian T. Bonham
Notary Public

February 13, 1960
My Commission Expires

PLUGGING
FILE SEC. 26 T. 29 R. 9W
BOOK PAGE 20 LINE 11