

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail of Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas.

WELL PLUGGING RECORD

Kingman County, Sec. 27 Twp. 29 Rge. 9 ~~W~~ (W)

Location as "NE/CNW%SW%" or footage from lines NE NE SW

Lease Owner Ben F. Brack Oil Company, Inc.

Lease Name Goetz Well No. 1

Office Address 309 Brown Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 1-15-56 19

Application for plugging filed 1-14-56 19

Application for plugging approved 1-14-56 19

Plugging commenced 1-15-56 19

Plugging completed 1-15-56 19

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes, verbally

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Arbuckle Depth to top 4653' Bottom _____ Total Depth of Well 4682' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface sand, Red Rock & Shale		0	290	8 5/8"	290	None
Heebner		3273				
Douglas Sand		3304				
Lansing		3495				
Mississippi		4148				
Kinderhook		4338				
Viola		4463				
Simpson		4532				
Arbuckle		4653	4682			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 270', set plug at 270' with 20 sax cement and hulls, filled with heavy mud to 35' and set plug at 35' with 10 sax cement and hulls. Levelled location.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ben F. Brack Oil Company, Inc.

Address 309 Brown Building, Wichita 2, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Bernard D. Grant (employee of owner) or (~~owner or operator~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bernard D. Grant

309 Brown Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of January, 19 56

Bertrude Crist
Notary Public.

My commission expires June 11, 1959

RECEIVED
STATE CORPORATION COMMISSION

JAN 20 1956

PLUGGING
FILE REC 27 T 29 R 9 W
BOOK PAGE 31 LINE 44

BEN F. BRACK OIL COMPANY, INC.
309-10 BROWN BUILDING
WICHITA 2, KANSAS

GOETZ #1

NE NE SW

Sec. 27-29E-9W
Kingman County, Kansas
Commenced: 12-26-55
Completed: 1-15-56

TOTAL DEPTH: 4682'
ELEVATION : 1593' DF
1590' Gr

WELL LOG

Sand	0 -	10'
Red Rock		15'
Sand & Shale		290
Shale		450
Red Bed, Shale & Shells		1000
Shale & Shells		1150
Anhydrite & Shale		1375
Lime & Shale		1565
Lime		1655
Lime & Shale		1690
Lime		1720
Lime & Shale		1960
Shale & Lime		2210
Lime & Shale		2380
Shale & Lime		2675
Lime & Shale		2770
Shale & Lime		2855
Lime & Shale		2944
Lime		2950
Lime & Shale		3272
Lime, Shale & Sand		3342
Sand & Shale		3487
Sand, Shale & Lime		3495
Lime		3659
Lime & Shale		3782
Lime		3860
Lime & Shale		4036
Shale & Lime		4148
Cherty Lime		4200
Lime		4212
Hard Lime		4231
Lime		4267
Lime & Chert		4310
Shale & Lime		4350
Shale		4462
Lime		4480
Hard Lime Chert		4500
Lime & Shale		4516
Shale & Sandy Shale		4572
Sand & Sandy Shale		4640
Shale		4655
Lime		4678' T.D. CORRECTED T.D. 4682' D & A

The above depths denote bottom of formations.

CASING

8 5/8" 290'

RECEIVED
JAMES W. BRACK

To the best of my knowledge, the above is a true and correct statement of the depths and formations and where found.

BEN F. BRACK OIL COMPANY, INC.

By Bernard Bryant

WITNESSED: Arthur Cust

PLUGGING
FILE SEC 27 29 9W
BOOK PAGE 31 LINE 44