

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County, Sec. 29 Twp. 29 Rge. 9 (E) W (W)

Location as "NE/CNW*SW*" or footage from lines SW SW

Lease Owner Morgenstern & Specter, Inc.

Lease Name Goetz Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 1-27-63 19

Plugging completed 2-1-63 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie Elving

Producing formation Depth to top Bottom Total Depth of Well 4429 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	360'	None
				5-1/2"	4429'	2951'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

RECEIVED
STATE CORPORATION COMMISSION

FEB 8 1963

CONSERVATION DIVISION
Wichita, Kansas

Checked hole to 4413', sanded to 4385' and dumped 5 sacks of cement @ 4385' with dump bailer. Pulled 5 1/2" casing, well blew in after 28th jt. Closed in well and pumped in 18 sacks of salt gel and 15 sacks of wt. mud, followed with 2 loads of water. Closed in well, still had gas. Pumped in 30 sacks of wt. mud and 23 sacks of salt gel. Killed gas and pulled Balance of 5 1/2" casing. Bailed mud to 200', set rock bridge to 190' and ran 20 sacks of cement @ 190'. Mudded to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss. Noel J. Knight

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight

Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of February, 1963

Milton J. Volin

My commission expires May 20, 1964

Notary Public.




WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company. CITIES SERVICE OIL CO.
Farm. Gochtz No. 1

SEC. 29 T. 29 R. 9W
NE SW SW
990' N 990' E SW cor.

Total Depth. 4429' PB 4413'
Comm. 11-2-56 Comp. 11-18-56
Shot or Treated.
Contractor. Barbour Drlg. Co.
Issued. 2-23-57

County Kingman
KANSAS



Elevation 1646' DF

Production. Pot. 2961 oil. NW
in 24 hrs.

Figures indicate Bottom of Formations.

shale-shells	370
red bed-shale	700
shale-shells	1355
Anhydrite	1380
shale-lime	1430
lime	1645
lime-shale	1770
lime	1950
lime-shale	2265
shale-lime shells	2465
shale	2635
shale-lime	2970
shale	3155
lime-shale	3500
shale-sand-lime	3570
lime	4190
chert	4205
lime	4219
lime-shale	4255
lime	4310
lime-shale	4400
lime	4432
Total Depth SIM	4429
PB	4413

RECEIVED
STATE CORPORATION COMMISSION

JAN 10 1963

CONSERVATION DIVISION
Wichita, Kansas

TOPS:

Corr. Lansing	3565
" Mississippi	4186
" Kinderhook	4216
" Viola	4389
Penetration	40

Drilled cement to 4413 SIM.

Loaded hole w/wtr.

Perf. 24 shots 4394-4400/

Acid 250 gals. 1-11-56