

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado De'by Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-095-00024-0000

LEASE NAME Goetz

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 29 TWP. 29 RGE. 9 (E) or (W)

COUNTY Kingman

Date Well Completed 9-18-56

Plugging Commenced 10-4-95

Plugging Completed 10-9-95

LEASE OPERATOR Bristol Resources Corporation

ADDRESS 6655 South Lewis, Ste. 200 Tulsa, Ok. 74136

PHONE#(918) 492-7900 OPERATORS LICENSE NO. 03048

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Jack Luthi (KCC District Agent's Name).

Is ACO-1 filed? if not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4474'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	237'	none
				5-1/2"	4473'	2226'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Plugged off bottom with sand to 4360' and 5 sacks cement. Shot pipe at 2500', @2300', and @2200'. Pulled to 1400', pumped 35 sacks cement. Pulled to 1000' pumped 35 sacks cement. Pulled to 410', pumped 170 sacks cement (60/40 4% gel. and circulated to surface. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 209 Chase, Kansas 67524

RECEIVED
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bristol Resources Corporation

NOV 1 1995

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P.O. Box 209 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 26th day of October, 19 95

Jane Herzberg
Notary Public

My Commission Expires:
USE ONLY ONE SIDE OF EACH FORM

