


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

KINGMAN County. Sec. 29 Twp. 29 Rge. 9W (E) (W)  
Location as "NE/CNW/SW" or footage from lines SE NE SW  
Lease Owner SANTA FE PIPE & SUPPLY  
Lease Name GOETZ # Well No. 2  
Office Address P. O. BOX 562 - GREAT BEND, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) OIL  
Date well completed OCTOBER 13 19 56  
Application for plugging filed JANUARY 7 19 64  
Application for plugging approved JANUARY 8 19 64  
Plugging commenced JANUARY 18 19 64  
Plugging completed JANUARY 23 19 64  
Reason for abandonment of well or producing formation DEPLETED

NORTH



Locate well correctly on above.  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well A. ELVING, PRATT, KANSAS  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4430' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	211'	NONE
				5 1/2"	4429.50'	3693'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

PLUGGED BACK WITH SAND FROM 4430' TO 4380'. MIXED AND DUMPED 5 SACKS CEMENT FROM 4380' TO 4340'. PULLED CASING. MUDDERED HOLE TO 270'. SET 10' ROCK BRIDGE FROM 270' TO 260'. MIXED AND DUMPED 25 SACKS CEMENT FROM 260' TO 185'. MUDDERED HOLE FROM 185' TO 40'. SET 10' ROCK BRIDGE FROM 40' TO 30'. MIXED AND DUMPED 10 SACKS OF CEMENT FROM 30' TO BASE OF THE CELLAR.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 20 1964

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor ACE PIPE PULLING COMPANY  
Address P. O. BOX 304 - GREAT BEND, KANSAS

STATE OF KANSAS COUNTY OF BARTON, ss.  
T. L. NUTT (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. L. Nutt  
P. O. BOX 562 - GREAT BEND, KANSAS  
(Address)

SUBSCRIBED AND SWORN to before me this 19th day of MARCH, 19 64

My commission expires JULY 31, 1966

Mary M. Guesnier  
Mary M. Guesnier Notary Public.

15-095-00568-0000


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company: PRYOR & TRACY & D & M DRILLING CO.  
Farm: Goetz No. 2

SEC. 29 T. 29 R. 9W  
SE NE SW

Total Depth. 4430  
Comm. 9-28-56 Comp. 10-13-56  
Shot or Treated.  
Contractor.  
Issued. 12-29-56

County Kingman KANSAS



CASING:  
8 5/8" 211' cem w/150 sx.  
5 1/2" 4429.50' cem w/100 sx.

Elevation. 1646

Production. 251 BOPD

Figures indicate Bottom of Formations.

shale, sand	40
sand, redbed, shale	500
shale, shells, lime	935
shale, shells	1145
anhydrite	1160
shale w/lime strks	1400
shale, lime	2071
shale s/lime strks	2245
shale, lime	2536
shale w/lime strks	2700
shale, lime	3702
lime	3798
lime, shale	3865
lime	3941
lime, shale, chert	4016
lime, shale	4394
lime, shale, chert	4430
Total Depth	

Tops: Scout  
Viola 4390

RECEIVED  
STATE CORPORATION COMMISSION

MAR 20 1964

CONSERVATION DIVISION  
Wichita, Kansas

RECEIVED

DEC 19 1963

Santa Fe Pipe & Supply