


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

KINGMAN County. Sec. 31 Twp. 29 Rge. 9W (E) (W)
Location as "NE/CNW/SW" or footage from lines NE NE NE
Lease Owner SANTA FE PIPE & SUPPLY
Lease Name GEORGE CARTER ESTATE Well No. 1
Office Address P. O. BOX 562 - GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) OIL
Date well completed JULY 19 19 57
Application for plugging filed NOVEMBER 29 19 63
Application for plugging approved DECEMBER 2 19 63
Plugging commenced DECEMBER 7 19 63
Plugging completed DECEMBER 12 19 63
Reason for abandonment of well or producing formation DEPLETED

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ARCHIE ELVING
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4435' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				9 5/8	300'	NONE
				5 1/2	4434'	3182'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED BACK WITH SAND FROM 4405' TO 4370'. MIXED AND DUMPED 5 SACKS CEMENT FROM 4370' TO 4330'. PULLED CASING. MUDDERED HOLE TO 290'. SET 10' ROCK BRIDGE FROM 290' TO 280'. MIXED AND DUMPED 25 SACKS CEMENT FROM 280' TO 205'. MUDDERED HOLE FROM 205' TO 40'. SET 10' ROCK BRIDGE FROM 40' TO 30'. MIXED AND DUMPED 10 SACKS FROM 30' TO BASE OF THE CELLAR.

RECEIVED
STATE CORPORATION COMMISSION

2-3-64 FEB 3 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor ACE PIPE PULLING COMPANY
Address P. O. BOX 304 - GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
T. L. NUTT (employee or owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. L. Nutt
P. O. BOX 562 - GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 31ST day of JANUARY, 19 64

My commission expires JULY 31, 1966

Mary M. Guesnier
Mary M. Guesnier Notary Public.

15-095-00577-0000

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company- **MAGNOLIA PETROLEUM CO.**
Farm-George Carter Est. No. 1

SEC. 31 T. 29 R. 9W
NE NE NE

Total Depth. **4435'**
Comm. **6-19-57** Comp. **7-19-57**
Shot or Treated.
Contractor, **Harry Bass Drilg. Co.**
Issued. **12-7-57**

County **Kingman**
KANSAS



Elevation. **1617' DF**

Production.State Pot. **481 BOFD**

CASING:
9 5/8" 300' cem w/275 sx.
5 1/2" 4434' cem w/200 sx.

Figures Indicate Bottom of Formations.

sand-shale	45
red bed - sand	293
sand - shale	301
red bed - shale	860
shale & shells	1370
shale - Anhydrite	1574
Anhydrite - lime	1712
lime & shale	3330
lime-sand-shale	3600
lime & shale	3644
lime 369	3691
lime & shale	4115
lime, shale & chert	4181
lime - chert	4197
lime-chert-shale	4250
lime & shale	4435
Total Depth	

TOPS:

Lansing-Kansas City	3537
Mississippi	4147
Kinderhook Shale	4209
Chattanooga Shale	4357
Viola	4385

DST #1 4387-98, open 1 hr., strong blow
gas in 10 min., TSTM, rec. 200'
oil, (gr. 39°), 175' G & MCO,
FP 40 - 120#, BHP 1295# SI 20 min.

RECEIVED
STATE CORPORATION COMMISSION

FEB 3 1961

CONSERVATION DIVISION
Wichita, Kansas