


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kingman County. Sec. 31 Twp. 29S Rge. 9W ~~XXX~~
Location as "NE/CNW 1/4 SW 1/4" or footage from lines _____
C-N/2 N/2 SE
Lease Owner Rex & Morris Drilling Co.
Lease Name Carter Well No. 1
Office Address 625 S. Main, El Dorado, Kansas 67042
Character of Well (Completed as Oil, Gas or Dry Hole) _____
Dry Hole



Locate well correctly on above
Section Plot

Date Well completed May 8, 1980
Application for plugging filed Verbal Application 19____
Application for plugging approved Verbal Approval 19____
Plugging commenced May 8, 1980
Plugging completed May 8, 1980
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well William T. Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4,260'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	408'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 4,260 ft. (rotary total depth) to 420 ft. Set plug at 420 ft. and cemented with 40 sacks cement. Filled hole with heavy rotary mud from 420 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 5 sack cement in rat hole.

Plugging operations accomplished utilizing Sun Oil Well cementing pump truck through 4 1/2 inch drill pipe.

RECEIVED
STATE CORPORATION COMMISSION
MAY 20 1980
67530
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sun Oil Well Cementing, Inc.
Box 169, Great Bend, Kansas

STATE OF Kansas COUNTY OF Sedgwick
Gary Younger, Agent (XXXXXX of owner) XXXXXXXXXXXXXXXXXXXXXXX

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gary Younger for Gary Younger
251 N. Water-Ste. 10, Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of May, 1980

Elsie Willison
Elsie Willison - Notary Public.

My commission expires July 25, 1982

KANSAS DRILLERS LOG

COMPANY Rex & Morris Drilling Co.

SEC. 31 T. 29S R. 9W

FARM Carter NO. 1

LOC. C-N/2 N/2 SE

COUNTY Kingman

ROTARY TOTAL DEPTH 4,260'

COMM. April 29, 1980 COMP. May 8, 1980

CONTRACTOR H-30, Inc. (Rig #3)

ISSUED May 19, 1980

CASING

10 3/4"

8 5/8" Set at 408' cemented w/275 sxs cement

ELEVATION 1,643' K.B.

5 1/2"

4 1/2"

FIGURES INDICATE BOTTOM OF FORMATIONS

Red Bed	410'
Red Bed and Shale	700'
Shale and Shells	963'
Lime and Shale	2,108'
Shale and Lime	2,326'
Lime and Shale	4,260'
Rotary Total Depth	4,260'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

RECEIVED STATE CORPORATION COMMISSION

Gary Younger MAY 20 1980 CONSERVATION DIVISION Wichita, Kansas

State of Kansas)
County of Sedgwick) ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 19th day of May, 1980.



Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:

July 25, 1982