


STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Give All Information Completely.  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County, Sec. 32 Twp. 29 Rge. 9 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE NW  
Lease Owner Morgenstern & Specter, Inc.  
Lease Name Heibsch Well No. 1  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 2-2-63 19  
Plugging completed 2-4-63 19  
Reason for abandonment of well or producing formation Depleted.

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving  
Producing formation Depth to top Bottom Total Depth of Well 4434 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	387'	None
				5-1/2"	4461'	3508'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 4420', sanded to 4390' and dumped 5 sacks of cement @ 4390' with dump bailer. Pulled 5 1/2" casing, mudded hole to 200', set rock bridge to 190' and ran 20 sacks of cement @ 190'. Mudded to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

FEB 13 1963  
STATE CORPORATION

PLUGGING COMPLETE.

FEB 13 1963 2-13-63

CONSERVATION DIV.  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 6th day of February, 1963

Milton J. Volin  
Notary Public.

My commission expires May 20, 1964



WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

15-095-00578-00000


COPY

Company- CITTES SERVICE OIL CO.  
Farm- Hebsch No. 1

SEC. 32 T. 29 R. 9W  
NE NE NW  
330' S 330' W N $\frac{1}{2}$  cor.

Total Depth. 4440' PB 4420'  
Comm. 8-9-57 Comp. 8-26-57  
Shot or Treated.  
Contractor. Barbour Drlg. Co.  
Issued. 1-25-58

County Kingman  
KANSAS



Elevation. 1627'

Production. 3000 BOPD

CASING:

8 5/8" 382' w/275 sx cem.  
5 1/2" 4434' w/150 sx cem.

Figures indicate Bottom of Formations.

sand	50
red bed-shale	1185
shale-shells	1520
shale-lime shells	1675
lime-shale	1845
lime	2075
lime-shale	2255
shale	2515
shale-lime	2985
lime	3080
lime-shale	3210
lime	3360
lime-shale	3380
shale-sand-lime	3500
shale	3551
lime	3985
lime-shale	4140
shale-lime-chert	4167
shale-lime	4185
chert	4215
chert-lime	4250
lime	4265
lime-shale	4305
shale	4355
shale-lime	4389
shale	4407
lime	4440

Total Depth 4440' - 4434 SLM  
PB 4420'

TOPS:

Corr. Heebner	3337
" Dodge	3351
" Douglas	3367
" Lansing	3545
" Mississippi	4163
" Kinderhook	4233
" Viola	4402
Pen.	32

Drilled cement to 4420 SLM

Perf. 37 shote 4401-10

JAN 10 1963

CONSERVATION DIVISION  
Wichita, Kansas