


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Kiowa

County. Sec. 32 Twp. 29 Rge. 9 (E) W (W)

NORTH

Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines NW NW

Lease Owner Morgenstern & Specter, Inc.

Lease Name Goetz

Well No. 2

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 2-10-63 19

Plugging completed 2-13-63 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving

Producing formation Depth to top Bottom Total Depth of Well 4404 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	408'	None
				5-1/2"	4437'	2879'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 4393', sanded to 4360' and dumped 5 sacks of cement @ 4360' with dump bailer. Pulled 38 jts. of 5 1/2" casing and pumped in 33 sacks of weight mud and 12 sacks of salt gel down surface pipe. Let set over night and pumped in 61 sacks of weight mud and 31 sacks of salt gel through 5 1/2" casing to kill gas. Pulled balance of 5 1/2" casing. Mudded hole to 200', set rock bridge to 190' and ran 20 sacks of cement @ 190'. Mudded to 40' set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

FEB 25 1963

CONSERVATION DIV.
WICHITA, KANSAS

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY

Address CHASE, KANSAS.

STATE OF KANSAS, COUNTY OF RICE, ss.

Noel J. Knight

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight

Chase, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of February, 1963

My commission expires May 20, 1964

Notary Public.

15-095-00580-0000
WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company- CITIES SERVICE OIL CO.
Farm- Goetz No. 2

SEC. 32 T. 29 R. 9W
NE NW NW
330° S 990° E NW cor.

Total Depth. 4410' PB 4393'
Comm. 7-20-57 Comp. 8-6-57
Shot or Treated.
Contractor. Barbour Drlg. Co.
Issued. 1-25-58

County Kingman
KANSAS



CASING:
8 5/8" 413' w/275 sx cem.
5 1/2" 4404' w/150 sx cem.

Elevation. 1606'

Production. 3000 BOPD

Figures indicate Bottom of Formations.

sand	40
red rock	160
shale-shells	415
red bed	475
shale-shells	1400
lime-shale	2325
shale	2525
lime-shale	3210
sand-lime	3230
lime	3338
lime w/shale stks	3355
sd. lime-shale	3470
shale-lime	3555
lime	4025
lime-shale	4111
cherty lime-shale	4136
lime-chert	4175
lime	4205
lime-shale	4367
lime	4410 = 4404'
Total Depth	
PB	4393

TOPS:
Corr. Lansing 3516
" Mississippi 4136
" Kinderhook 4199
" Viola 4368
Pen. 36

Drilled cement to 4393 SLM

Perf. 44 shots 4370-81, gas to
surface in 6 min. Flow oil in 2 1/2 hrs.

RECEIVED
STATE CORPORATION COMMISSION

JAN 10 1963

CONSERVATION DIVISION
Wichita, Kansas