

Y KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued January 29, 1968.

RECEIVED
STATE CORPORATION COMMISSION
JAN 31 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 Fourth National Bank Bldg., Wichita, Kansas 67202

Lease Name Cox "B" Well No. # 1

Location SW SE SE Sec. 24 Twp. 29 Rge. 7 (E) (W)W

County Kingman Total Depth 4505'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Russ Casing Pulling, Inc.

Address: Box 1082, Great Bend, Kansas 67530 License No. 623

Operation Completed: Hour 10:00AM Day 30th Month January Year 1968

The Above well was plugged as follows:

280' of 8 5/8" surface pipe, cement circulated. 4503' of 5 1/2" long string,
cemented with 100 sacks. Top perferation 4088'. 40 sacks of cement was pumped
on bottom, with the top of the cement at 4068'. 3410' of 5 1/2" long string
was recovered from the hole. Hole was filled with mud to 300', rock bridge
from 300' to 290', and cemented with 25 sacks, with cement from 290' to 215',
Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented
with 10 sacks, with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 1/31/68

INV. NO. 7181-W