

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 8 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 Fourth National Bank Bldg., Wichita, Kansas

Lease Name Millard "B" Well No. # 1

Location NE NE SW Sec. 25 Twp. 29 Rge. 7 (E) (W)W

County Kingman Total Depth 4225'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Flint Engineering & Construction Company

Address: Box 950, El Dorado, Kansas License No. 547

Operation Completed: Hour 12:00PM Day 5th Month Dec. Year 1966

The Above well was plugged as follows:

243' of 8 5/8" surface pipe, cemented with 190 sacks. 4221' of 5 1/2" long
string, cemented with 125 sacks. Top perferation 4149'. Bottom of the hole
was sanded to 4100', and cemented with 5 sacks, through the dump bailer.
3350' of 5 1/2" long string was recovered from the hole. Hole was filled with
mud to 240', rock bridge from 240' to 230', and cemented with 25 sacks.
Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented
with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Aubie Elving
Well Plugging Supervisor

DATE 12/9/66

INV. NO. 4423-W