

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 6 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Kathol Petroleum Inc

Complete Address 900 Sutton Place Wichita, KS

Lease Name Millard Well No. 1

Location SE/NE/SW Sec. 25 Twp. 29 Rge. 7 (E) (W) W

County Kingman Total Depth 4130

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Ralph Comstock Pipe Pulling Co. Inc

Address Stafford, KS License No. 490

Operation Completed: Hour 10:00 AM Day 3 Month 2 Year 1973

The above well was plugged as follows:

250 ft 8 5/8 surface cemented with 200 sacks. 4129 ft 5 1/2 long string
cemented with 150 sacks. Top perf. 3708 ft. Sand to 3675 ft. 5 sacks
cement with bailer. Pulled 3100 ft 5 1/2. Set 10 ft rock bridge at
280 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 2/7/73

INV. NO. 6945-W