

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 20 1970  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Pickrell Drlg. Co.

Complete Address 705 4th Natl. Bldg. Wichita, Ks

Lease Name Maple E Well No. 1

Location SW/SW/NW Sec. 25 Twp. 29 Rge. 7 (E) (W) W

County Kingman Total Depth 4270

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Russ Casing Pulling Co. Inc.

Address Box 1082 Great Bend, Ks License No. 623

Operation Completed: Hour 5:00 PM Day 18 Month 8 Year 1970

The above well was plugged as follows:

261 ft of 8 5/8 surface pipe cemented with 105 sacks. 4268 ft of  
5 1/2 long string cemented with 90 sacks. Top perf. 4165 ft. Sand  
back to 4150 ft, 5 sacks cement with bailer. Pulled 3516 ft of 5 1/2.  
Set 10 ft rock bridge at 220 ft. & fill hole with 3 1/2 yds redimix.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 8/20/70

INV. NO. 2413-W