

*JP*  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

SEP 30 1963  
9-30-63  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Tenneco Oil Co.

Complete Address: 2000 Classen Bldg., Oklahoma City, Oklahoma

Lease Name Byron E. Pruitt Well No. # 1

Location NE SW Sec. 34 Twp. 29 Rge. 6 (E) (W) W

County Kingman Total Depth 4151

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Strata Drilling Inc.

Address: 2421 Tenth St., Great Bend, Kansas License No.     

Operation Completed: Hour 5:30AM Day 28th Month Sept. Year 1963

The Above well was plugged as follows:

257' of 8 5/8" surface pipe, cemented with 225 sacks. Hole was filled  
with drilling mud to 250', 1st cementing plug, bridged with 1/2 sack hulls,  
cemented with 25 sacks. Hole was filled with drilling mud to 40', 2nd  
cementing plug, bridged with 1/4 sack hulls, cemented with 10 sacks to  
base cellar. Rat hole bridged and cemented with 2 sacks. Mouse hole  
bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

*INV 0100 ED*  
DATE 9/30/63  
INV. NO. 9819-W

Signed: Audine Elving  
Well Plugging Supervisor