

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 3 1975
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Petroleum Inc

Complete Address Rt 2 Great Bend, KS

Lease Name Early C Well No. 1

Location C SW/SE Sec. 28 Twp. 29S Rge. 6 (E) (W)

County Kingman Total Depth 4560

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Pipe Pullers Inc

Address Box 218 Ellinwood, KS License No. 462

Operation Completed: Hour 10:00 AM Day 31 Month 10 Year 1975

The above well was plugged as follows:
248 ft 8 5/8 surface cemented with 200 sacks. 4553 ft 4 1/2 long string
cemented with 125 sacks. Top perf. 4494 ft. Sand to 4450 ft, 4
sacks cement with bailer. Pulled 3460 ft 4 1/2. Set 10 ft rock bridge
at 300 ft. Fill hole with 5 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 11/3/75

INV. NO. 2163-W