

15-095-20157-0005
JL

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 14 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Santa Fe Pipe & Supply Inc.

Complete Address Box 562 Great Bend, Ks

Lease Name Port Early Well No. 2

Location SW/NE/SE Sec. 28 Twp. 29 Rge. 6 (E) (W) W

County Kingman Total Depth 4800

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated

Plugging Contractor Santa Fe Pipe & Supply Inc.

Address Box 562 Great Bend, Ks License No. 574

Operation Completed: Hour 10:00 AM Day 10 Month 6 Year 1971

The above well was plugged as follows:

258 ft 9 5/8 surface pipe cemented with 180 sacks.

4502 ft 5 1/2 long string Cemented with 250 sacks. Liner set at 4427 ft.

to 4800 ft. Top perf. 4785 ft. Pushed plug to 4427 ft. Sand back to

4415 ft, 5 sacks cement with bailer. Pulled 2803 ft 5 1/2. Set 10 ft

rock bridge at 240 ft. Fill hole with 5 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 6-14-71

INV. NO. 3852-W