

15-095-01576-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 11 1965

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Howard Alexander

Complete Address: Kennedy Bldg., Tulsa, Oklahoma

Lease Name Davis Well No. # 2

Location SE SE SE Sec. 32 Twp. 29 Rge. 6 (E) (W) W

County Kingman Total Depth 3750'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Self Casing Pulling Company

Address: Route 4, Hutchinson, Kansas License No.

Operation Completed: Hour 10:30AM Day 8th Month Oct. Year 1965

The Above well was plugged as follows:

187' of 8 5/8" surface pipe, cement circulated. 3749' of 5 1/2" long string,
cemented with 100 sacks. This is an open hole. Bottom of the hole was
sanded to 3740', and cemented with 5 sacks. 3040' of 5 1/2" long string was
recovered from the hole. Hole was filled with mud to 200', rock bridge
from 200' to 190', and cemented with 3 yards of Ready-Mix cement to
the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED
DATE 10/11/65
INV. NO. 1959-W